

Arvada Fire Protection District
Division of Fire Prevention
Fire Alarm System Plan Review
Checklist/Requirements/Inspections
City of Arvada

It is the responsibility of the designer/installer of record to assure that all applicable code requirements are adhered to. The 2006 edition of the International Fire Code, as amended, and with the associated National Fire Protection Association Standard 72, 2007 edition shall be the primary, but not all inclusive, resource documents.

The installation, addition, renovation, and maintenance of any fire alarm system shall comply with the following:

Contractors License:

Fire alarm system companies and installers shall be licensed with the Building Inspection Division of the City of Arvada.

Plan Review Fees:

Plan review fees are collected by the Building Inspection Division of the City of Arvada. Building Permit fees are based upon plan review fees and use tax are based upon the valuation of the job. For questions on permit fees please contact the Building Inspection Division at 720-898-7620.

Plan Submittal:

Plans may be submitted at the City of Arvada Building Inspection Division, 8101 Ralston Road, Arvada, CO 80002. The Building Inspection Division is located on the Second Floor. Plans may be submitted Monday through Friday 8:00 AM to 4:30 PM. Plans will then be forwarded to the Division of Fire Prevention for review and comment. Upon completion of the plans review, two (2) sets of plans will be returned to the Building Inspection Division for your permit.

Plan Approval:

No installation work shall be performed until the submitted plans are reviewed and approved by the Division of Fire Prevention.

Plans are reviewed in the order in which they are received. Please submit your plans as soon as possible. Fire alarm plans are normally reviewed within ten (10) business days. The Division of Fire Prevention works ten (10) hour days, four (4) day work weeks. If work loads dictate a longer plan turnaround, the Division of Fire Prevention will notify the designer/installer of the additional time for plans review and approval is necessary.

Expedited Plan Reviews:

The Division of Fire Prevention does not conduct expedited plan reviews.

Fire Alarm System Plans:

__Submit three (3) sets of fire alarm system plans and three (3) sets of cut/sheet product information.

__Two (2) sets of stamped plans shall be returned to the designer/installer. One set of stamped plans with the notation, "THIS SET OF PLANS IS TO REMAIN AT THE JOB SITE" is required to be at the site at all times for inspections.

__A minimum level NICET II designer for fire alarm systems must stamp the plans.

__Plans need to be clear and understandable. Plans must be of the fire alarm design only. NO combination drawings using reflected ceiling plans, mechanical, etc. will be accepted.

__Drawings shall be scaled. We would request 1/8 inch equals 1 foot scale.

__Plans shall include one line and riser diagrams for all devices, notification circuits, auxiliary circuits, initiating circuits, circuit designation and central station connect.

__Fire alarm panels shall be provided on a dedicated circuit. The circuit breaker for the fire alarm panel shall be red and identified as "Fire Alarm Panel". A circuit breaker lock shall be placed on fire alarm circuit.

__All symbols utilized shall be indicated in a complete legend positioned on the plans.

__Ceiling heights must be identified on the plans.

__Ceiling construction (e.g., flat, sloped smooth, joist/beam etc.) must be identified on the plans.

Specification (Cut) Sheets:

All pertinent Information Shall be Highlighted on Sheets.

Construction documents for fire alarm systems shall include, but not limited to, all of the following:

__A floor plan which indicates the use of all rooms.

__Location of alarm-initiating and notification appliances.

__Type of Detectors to be installed.

(Smoke Detectors) Photoelectric /Ionization/ Beam/etc.

(Heat Detectors) Fixed Temperature/Rate of Rise/etc. (Listed Temperatures).

__Manual Pull Stations.

__Remote indicating devices.

__Alarm control and trouble signaling equipment.

__Annunciation.

__Power connections.

__Battery calculations.

__Conductor type and sizes.

__Voltage drop calculations.

__Manufacturers, model numbers, and listing information for equipment, devices and materials.

__Details of ceiling height and construction.

__Interface of fire safety and control functions.

__Water flow devices.

__Supervisory valve monitoring.

Low air monitoring.

Pre-Action systems.

Dry Pipe Systems

Fire Pumps.

Outside horn and light type, location. Outside horn and light shall activate upon water flow only.

Fire extinguishing systems monitoring.

Clean agent systems.

Duct detection and monitoring.

Smoke control systems.

Pre-action systems.

Additional Submittal Information Required:

UL Listed Supervising Station name or Remote Station

Number of dedicated telephone lines to the monitoring station.

Radio or DSSL Lines.

Graphic Map with initiating device locations.

Measured or Estimated Ambient Sound Levels used.

Identification of Devices:

All detectors, pull stations, control valves, extinguishing systems, etc. shall be identified with the corresponding address number noted on the panel and or graphic map.

Audibility Tests:

Audibility tests shall be conducted by the installer/designer prior to final inspection and a copy of the test results shall be provided to the Division of Fire Prevention at the time of the Final Inspection.

Submittal of As- Built Plans:

Prior to the final inspection of the building or unit, as-built plans (if any changes from the approved plans) are required due to changes in construction.

Inspections:

Rough wiring and location inspections will need to be conducted by the Division of Fire Prevention and the Electrical Inspector for the City of Arvada, and any necessary corrections completed and re-inspected prior to the concealment of work.

Twenty-four (24) hours notice is required for all inspections and tests. Available days and inspection times will be noted on the approved plans.

Requirments prior to the Final Inspection of the Fire Alarm System:

No acceptance testing shall be conducted by the Division of Fire Prevention prior to the completion of construction within the building or units.

Final inspections are subject to field inspection.

Record of Completion:

Three (3) copies of the Record of Completion as outlined in NFPA 72 shall be completed and be ready for signatures upon completion of acceptance tests.

Re-Inspection Fees:

Re-inspection fees will be charged for re-inspections needed due to incomplete fire alarm systems, failure of tests, and conditions that should be corrected prior to inspection.